



No.	CAT	UNITS	Qty.	NOTE	Price	Engineering		Procurement		Construction		
					USD	PCCS	Client	PCCS	Client	PCCS	Client	
1	Design	FEED & DED	1	Including general contracting management fees	550,000	✓	x	✓	x	✓	x	
2	Process Unit	Feed gas Inlet Device	1	Capacity:5MMSCFD , separator, shut-off valve, filter, heat exchanger, etc Feed gas pressure more than 4.0MPaG	115,000	✓	x	✓	x	✓	x	
3		Acid Gas Removal Unit	1	The CO2 content in Feed Gas less than 2%	935,000	✓	x	✓	x	✓	x	
4		Dehydration Device	1		725,000	✓	x	✓	x	✓	x	
5		Heavy Hydrocarbon Removal Device	1		295,000	✓	x	✓	x	✓	x	
6		Cold Box	1		650,000	✓	x	✓	x	✓	x	
7		Refrigerant Compressor	1		1,580,000	✓	x	✓	x	✓	x	
8		Heat exchanger Separation Device	1		380,000	✓	x	✓	x	✓	x	
9		Refrigerant makeup SKID	1		225,000	✓	x	✓	x	✓	x	
10		BOG Compressor	2		108,000	✓	x	✓	x	✓	x	
11		LNG storage and transportation unit	LNG Tank	6	150m³ ,Operating pressure0.15MpaG,Design pressure0.8MPag	810,000	✓	x	✓	x	✓	x
12	Condensate Tank		1	100m³ ,Operating pressure0.6MpaG,Design pressure1.0MPag	51,000	✓	x	✓	x	✓	x	
13	LNG Loading Pump SKID		1	80m3/h	175,000	✓	x	✓	x	✓	x	
14	Condensate Loading Pump		2	30m3/h	57,000	✓	x	✓	x	✓	x	
15	LNG Loading SKID		1	Equipped with metering, shut-off valve, etc.; flow rate: 80m3/h,2 loading hoses	250,000	✓	x	✓	x	✓	x	
16		Condensate Loading SKID	1	Equipped with metering, shut-off valve, etc.; flow rate: 30m3/h,2 loading hoses	85,000	✓	x	✓	x	✓	x	
17	Utility Facility	Instrument Air and Nitrogen Producing Device	1		135,000	✓	x	✓	x	✓	x	
18		Desalinated water Device	1		55,000	✓	x	✓	x	✓	x	
19		Heat transfer Oil Heating Device	1		125,000	✓	x	✓	x	✓	x	
20		Cooling tower	1		136,000	✓	x	✓	x	✓	x	
21		Circulating Water Pump	3		24,000	✓	x	✓	x	✓	x	
22		Booster Water Pump	2		6,000	✓	x	✓	x	✓	x	
23		Analyzer system	1	CO2, water dew point	80,000	✓	x	✓	x	✓	x	
24		Flare system	1	Simple Torch	225,000	✓	x	✓	x	✓	x	
25			Control system	1	Including DCS/ESD system	425,000	✓	x	✓	x	✓	x
26			lighting system	1	Including explosion-proof lighting fixtures, explosion-proof lighting boxes, explosion-proof installation accessories, and other lighting materials	35,000	✓	x	✓	x	✓	x
27		Grounding System	1	Including grounding materials such as galvanized angle steel and galvanized flat steel, as well as equipment such as electrostatic alarm devices	36,000	✓	x	✓	x	✓	x	
28		Fire protection device	1		325,000	✓	x	✓	x	✓	x	
29		Fire Water Tank	1		80,000	✓	x	✓	x	✓	x	
30		Gas generator Set	1	Output Power: 2500kw	800,000	✓	x	✓	x	✓	x	
31		Power Transformation And Distribution	1	Including high-voltage transformation and distribution, low-voltage distribution	350,000	✓	x	✓	x	✓	x	
32		Emergency diesel generator set	1	Rated power 100kW 0.4kV, outdoor with silent machine room	17,000	✓	x	✓	x	✓	x	
33		Weighbridge	1	80T	28,000	✓	x	✓	x	✓	x	
34	Civil	Process equipment area	1	The road leading to the LNG loading zone shall be a simple unpaved road instead of a concrete road.	955,000	✓	x	✓	x	✓	x	
35		Office and living areas	1	PCC is responsible for the design and construction of the office(less than 300m²), dormitory(less than 600m²), and security room(less than 100m²), no power grid)	390,000	✓	x	✓	x	✓	x	
36		others	1	Site clearance, fencing, sandfilling, piling, geotechnical survey, Water quality report	-	x	✓	x	✓	x	✓	
37	Installation		1	Installation of all equipment and installation materials within the process unit area.	1,177,000	✓	x	✓	x	✓	x	
38	Commissioning	Manpower	1	Pcc shall provide commissioning supervision personnel, and the client shall supply the operators in accordance with the staffing requirements specified by the PCCS.PCC shall provide 3 commissioning engineers for a 30-day service period.	72,000	✓	x	✓	x	✓	x	
39		Commissioning materials	1	Refrigerant, lubricant, Transformer oil, molecular sieves, Specialized Acid Removal Absorbents.Excluding feed gas, water and electricity.	883,000	✓	x	✓	x	✓	x	
40		Logistics	1	Shipping cost from China to Nigerian Port	700,000	✓	x	✓	x	✓	x	
41	Transportation	Nigerian local transportation	1	The Owner/client shall be responsible for custom clearance at the port of delivery (Apapa or other port) and shall be responsible for transporting all equipment from the port of delivery to the project site. The Owner/client shall bear all the cost including transportation, security, insurance, etc.	-	x	✓	x	✓	x	✓	
42	Public Relationship and security	Government/ Community Relations Work	1	The Owner/client shall be responsible for all community related cost and community relations; armed military personnel, and shall be responsible for procurement of all statutory and government permits, waiver and authorizations (including but not limited to EIA, NMDPRA Permits, HAZOP etc.),The safety of all personnel and materials involved is the responsibility of the owner.The client is responsible for providing the land required for project construction, handling certificates and procedures related to the government such as usage certificates and safety production	-	x	✓	x	✓	x	✓	
Excluding Tax Total(CIF)					14,050,000							
Remarks	Boundary: The external connection point of the liquefaction unit is the boundary between the two parties, and all pipelines outside the boundary are completed by the customer. The contract amount is based on the above supply scope and specifications. The above devices are designed according to GB standards. The prices of manpower and materials provided by the community need to be adjusted according to market prices, and any prices exceeding the market price will be paid by the Owner/client. Any fees charged by the community for the transportation of materials required for the project shall be paid by the Owner/client.Piping materials and installation work between the natural gas main pipeline and the Feed gas Inlet Device are not included.											